

EDF Nuclear plant under decommissioning programme

CIDEN organization

Projects achievement







• EDF Nuclear plant under decommissioning programme

• CIDEN Organization





EDF Nuclear plants in France

In operation : 58 PWR nuclear plants





34 PWR 900 MW 20 PWR 1300 MW 4 PWR 1450 MW

On 19 sites

PWR : Pressurized water Reactor



EDF nuclear plants under decommissioning

> 9 reators under decommissioning

<u>1 "Pressrized water reactor (PWR)</u> Chooz A (300MW) : 1967-1991

1 Heavy water reactor

Brennilis (70 MW) : 1967-1985 (EDF/CE

6 Gaz graphite reators (UNGG)

Chinon A1 (70MW) : 1963-1973 Chinon A2 (200MW) : 1965-1985 Chinon A3 (480MW) : 1966-1990 Saint-Laurent A1 (480MW) : 1969-1990 Saint-Laurent A2 (515MW) : 1971-1992 Bugey 1 (540MW) : 1972-1994

1 Fast Breeder reactor

Creys-Malville (1240MW) : 1986-1997

Graphite sleeves silos at St Laurent A



Decommissioning strategy (1)

- To perform total decommissioning of 9 reactors within 25 years in tow waves
 - ✓ 8 reactors so called "first generation reactors"
 - ✓ Creys-Malville
- □ First wave of decommissioning gathering :
 - ✓ Brennilis,
 - ✓ Creys-Malville,
 - ✓ Chooz A,
 - ✓ Bugey 1,
- Second wave of decommissioning with

✓ the last 5 GGR (Chinon A1, A2 et A3, Saint-Laurent A1 et A2).

✓ And graphite sleeves retrieval from St Laurent silos.





Decommissioning strategy (2)

Decommissioning chronology is based on the following considerations :

□ For Brennilis, EDF and CEA undertook to do decommissioning by the horizon 2015 therefore Brennilis must be inside the first wave,

Creys.Malville belong to the first wave for the same reason with a decommissioning schedule over 25 years,

Chooz A, is the only PWR reactor and belongs to the first wave as regard to the strategic impact of PWR decommissioning feed back,



GGR - Decommissioning strategy (3)

Gaz Graphite Reactors have technical and waste generic aspects :
Regarding graphite retrieval and treatment.



Bugey SG interrated technology, assuming that cecommissioning difficulties will cover all GGR decommissioning issues,

The good progress of level 2 working phases allowing to prepared easily the level 3 working phases,





GGR – Decommissioning strategy

- GGR under water decommissioning with Bugey first in line for St Laurent A1 and A2, Chinon A3
- GGR on air decommissioning with Chinon A2 first in line for Chinon A1

• Strategic port folio issued 2004 and revised 2009

Five "rules" have been guiding the GGR strategy • EDF attitude since 2004

• Strategic port folio include an internal structure resistance justification

• Graphite retreival « not after the year 2022 horizon »

• Writing from French safety authority dated April 2010

• Graphite retrieval in serie to avoid the futur disposal center saturation





Decommissioning programme









• EDF Nuclear plant under decommissioning programme

Old CIDEN Organization





12





CIDEN Project management

Baker Engineering division director

Strategic program management CIDEN deputy director

Operational project management Project manager

CIDEN Organization IS focusing on project management with supporting structure



Reporting

CIDEN Organization



EDF/JAPC COOPERATION AGREEMENT

Reporting - Data management at various levels Strategic level, for CIDEN management and backer

- Long term vision (scheduling, reference costs, waste, technical reference scenario)
 - A data book updated every 3 years : strategic scheduling, important hypothesis, expenses, engineering and operation resources, waste production by project and sub project and spreading until the end of project
 - Risk and solution analysis
 - Prepared by program manager and project managers
 - Project agreement by project

• Mid term vision (5 years) : Mid Term Plan include key stones and allocated resources

- Global indicators allowing to control the projects evolution and data book adequacy: working and financial progress
- Consolidated by program management
- Risk review (semester)

• Annual vision N+1 : Annual Achievement Contract includes annual important step and allocated resources

 Monthly checking of business indicators (program management), project expenses and hours (financial support)

Reporting - Data management at various levels

- Program/project level for CIDEN management
 - Annual peer review (project team), quarterly project management chart examination, quarterly report (Program management)
- Operational level, for project manager and project team
 - Studies and works plan allowing resources allocations on each projects (project team)
 - Project scheduling quarterly updated according with resources allocations (planner, program management)
 - Project expenses monthly checking and new forecasting (financial support)
 - Project technical progress checking : significant actions (hierarchy, technical department)
 - Project risk management (action plan, progress): project team Lotus Notes software
- Short term operational level, for project team and technical department
 - Project weekly meeting to coordinate short term operations
 - Work detailed scheduling update (site, weekly basis)
 - As much as necessary treatment of real time issues (by useful means)



Planning used for project management

Project planning software Planisware (OGOPA), with miles stone planning sharing



Project quarterly management chart : global management

Oigest data from various CIDEN structures and purchasing division





Deadline, achievement and cost

Management chart include 6 charts for each project :

Deadlines

 Work indicators and project miles stone control

Achievement

- Project work and financial progress
- Significant actions achievement
- Important contract and call for bid up to respectively 4,5 M€ et and 3 M€

October Costs

 Realized purchase and others expenses



iource des don nées es chilfres sont fournis par MGF (Annexe 3 du

edf

porting programme : état des reprises sur



Contribution du

chats MGF) ecture .e trimestre en cous est

iéré en orange ≈montants sont en k€

Work and finance progress indicator

- Solution Following baker requirement work progress indicator is calculated and issued on a quarterly basis
 - Subproject ratio is proportional to its financial ratio within the project
 - Each subproject includes limited representative tasks or operations. Progress measurement is based on unit of work (%, miles stone, waste weight), with a ratio proportional to the task or operation cost within the subproject
 - Passed mile stone are recorded and compare to the program reference and the new forecast (Excel file)
- Work progress indicator is compared to the project financial progress ratio
- Allow to globally know if projects and programme are progressing in the same way and if expenses progress is coherent with works progress (time evolution comparison)







• EDF Nuclear plant under decommissioning programme

OCIDEN Organization



Project regulatory achievement

Project	Authorisation/safety case file issue	Public enquiry	Decommissioning /creation decree
Creys Malville	06/05/03	April 04	21/03/06
Brennilis	25/07/08	October 09	27/07/11 (partial)
Chooz A	30/11/04	August 06	29/09/07
Bugey 1	29/09/05	August 06	20/11/08
St Laurent A	11/10/06	January 07	18/05/10
Chinon A3	29/09/06	March 07	18/05/10
ICEDA	05/10/05 (creation)	June 06	23/04/10 (creation)
Chinon A1 A2*	/	/	/

*Plants in care and maintenance situation

