

Radiological Characterization and Decommissioning in Denmark

Thomas Kjøller Nellemann

- M.Sc. in Physics and Nanotechnology, Technical University of Denmark (DTU)
- Danish Decommissioning, Production Engineer, Inventory Calculation
- Radiological Characterisation, April 2012, Studsvik.




- DD and Nuclear Facilities
- Sampling
- Inventory and Outlook




Danish Decommissioning

- Decommissioning
- Radioactive Waste
 - Receive
 - Handling
 - Storing
- Health Physics




Danish Reactors

- DR1
 - 1957-2001 (2006), 2 kW
- DR2
 - 1957-1975 (2008), 5 MW, Light water
 - Research, Production
- DR3
 - 1960-2000, 10 MW, Heavy Water
 - 2012: Design, Tendering Equipment



Hot Cell Decontamination

- Operation 1964-1989
- "Cleaned" and Sealed 1993
- High Doses and Offices Nearby




- DD and Nuclear Facilities
- **Sampling**
- Inventory and Outlook



Sampling or Modelling?

- Modelling not as precise or fast as Sampling
- Complex systems, Variable Waste - Hard to Model
- Both Sampling and Modelling?



Sampling Process



Sampling in Danish Decommissioning

- Cradle-to-Grave Work Planning
- Samples Representing Sorted Waste
- Ad Hoc Procedures for Dismantling



- DD and Nuclear Facilities
- Sampling
- **Inventory and Outlook**



Calculation of Inventory - Scaling

Induced activity can be calculated by this equation:

$$q(\text{tirr}, \text{tdecay}) = \frac{N}{A} \cdot \frac{a}{100} \sigma \cdot \phi \cdot \left(1 - \exp\left(\frac{-\ln(2)}{\text{thalf}} \cdot \text{tirr}\right) \right) \cdot \exp\left(\frac{-\ln(2)}{\text{thalf}} \cdot \text{tdecay}\right)$$

Scale factors can be defined as:

$$\text{SF}(\text{tirr}) = \frac{a}{A} \cdot \sigma \cdot \left(1 - \exp\left(\frac{-\ln(2)}{\text{thalf}} \cdot \text{tirr}\right) \right) \cdot \exp\left(\frac{-\ln(2)}{\text{thalf}} \cdot \text{tdecay}\right)$$



Examples of Scaling Factors

- Normalisation to a key nuclide
- Contamination scaling factors based on Sampling and measurements

Activation - Isotopes	DR3 Steel: Co-60 Scaling factors
Ni-63	12,01
Fe-55	6,067
Eu-152	2,792
Ba-133	0,4873
Cl-36	0,3814
Eu-154	0,1497
Ni-59	0,1270

Contamination - Isotopes	Hot Cell: Cs-137 Scaling factors
Pu-241	1,574
Sr-90	0,535
Pu-238	0,114
Am-241	0,093
Pu-239	0,054
Pu-240	0,041
Cm-243	
Cm-244	0,035



Summary & Outlook

DD Practice

- Decommissioning yield Variable Waste
- Sampling over Modelling when Possible
- Cradle-to-Grave Planning
- Ad Hoc Procedures as Needed






DR1




- Operated 1957-2001 – 2 kW
- Decommission completed in 2006



DR2

- Operation: 1957-1975
- 5 MW Light Water Reactor
- Research and Production of Isotopes
- Decommissioned 2005-2008



DR3

- Operation: 1960-1999
- 10 MW Heavy Water Reactor
- 2012: Design, Tendering Equipment, External Parts

