



Radiological Characterization of V1 NPP Technological systems & Buildings - Activation

Workshop on Radiological Characterisation for Decommissioning,
17 – 19 April, 2012, Studsvik, Sweden

Kristína Krištofová¹
Tibor Rapant¹
Jaroslav Svitek²
1 - AMEC Nuclear Slovakia s.r.o.
2 - JAVYS a.s.

kristina.kristofova@amec.com
tibor.rapant@amec.com
svitek.jaroslav@javys.sk



V1 NPP at Jaslovské Bohunice site



V1 NPP decommissioning:

- 2 WWER type reactor 440/230 units
- Operation: **Unit 1 in 1978 – 2006, Unit 2 in 1980 - 2008,**
- Since 2001 D&D preparation supported by Bohunice International Decommissioning Support Fund (BIDSF)
- At present: **units** finally shutdown, since July 2011 **under decommissioning license**

BIDSF Project B6.4

“Decommissioning Database”

Project purpose: Physical and radiological inventory database development to support V1 NPP decommissioning

Performed by: EWN GmbH, STM Power and AMEC Nuclear Slovakia

Project period: 2008 – 2011


Project tasks:

1. DDB design
2. Historical site assessment
3. Physical inventory – plan and performance
4. Sampling and analysis - plan and performance
5. Hazardous material inventory
6. **Activation inventory** - Characterization of Activated Components Based on Measurement and Sampling
7. Radiological inventory

Scope of inventory:

Nearly 100 civil objects
175 technological systems
Over 40 parameters for each DDB item - identification, physical and radiological properties

Subject of Activation Inventory




Works carried out in period from 04/2011 to 12/2011

Radiological Characterization of Activated Components

Scope of services:

1. **Categorization** of activated components – totally 112 samples planned
2. Development of single **working programs** for radiological monitoring and sampling
3. Preparation of **sampling device** & revision of NPP handling equipment
4. **Dose rate monitoring and sampling**
5. **Analyses** of samples: gammaspectrometry, radiochemical analyses; γ RA nuclides & limited RA nuclides for Mochovce repository
6. Determination of **radiological inventory**: activation values (Bq), RNV, dose rates
7. **Import** of radiological data for activated components **into DDB**

Sampling of activated civil structures in reactor concrete shaft of Unit 1 and 2



Number of drills: 8
(1- 4 at Unit1, 5-8 at Unit 2)
Sampling depth: 20 – 40 cm
Manual drilling device

Results:



- major activation RA nuclides:
Fe-55, H-3, Co-60, Eu-152,
Eu-154, Cs-134, **Ba-133**, Ni-
59, Ni-64, C-14
- contamination of concrete by
Cs-137
- Division of concrete to **9
layers/** unit (along RPV
concrete shaft height)

Sampling of activated concrete – results


V1 NPP concrete radiological inventory determined for 1.1.2010:

| Material | Standard concrete | Baryte concrete | Total |
|---------------|-------------------|-----------------|-----------------|
| Activity (Bq) | 1,58E+09 | 6,41E+08 | 2,22E+09 |
| Mass (kg) | 344 166 | 86 490 | 430 656 |

RNV – activated concrete for Unit 1:



Sampling of activated components in V1 NPP HLW storage (1)



V1 NPP HLW storage (399 cells):

- 157 absorbers of safety and control rod assemblies (ABS)
- 217 connection rods of safety and control rod assemblies (CR)
- over 330 pc of neutron flux measurement channels (KNI)

Procedure:

1. Categorization of stored components – **40 components selected**
2. Remotely controlled sampling equipment used
3. Existing NPP equipment for manipulation – transport containers for components

Sampling of activated components in V1 NPP HLW storage (2)

Sampling procedure in HLW storage:

- Remote-controlled equipment with drilling head on linear guiway, sample suction into carousel
- **80 samples taken** from selected components (ABS, CR, KNI) – **swarfs**
- Sample mass from 0.6 mg to 900 mg
- **Dose rate monitoring** along the height of component – **up to 30 Sv/h** at sampling spot




Sampling of activated connection rod in V1 NPP HLW storage - video



Sampling of activated components in V1 NPP HLW storage – results (1)

| Category | Dose rate interval [mSv/h] | Assignment of activated component part into category | | | |
|----------|----------------------------|--|-----------------------|----------------------------------|------------------------------|
| | | CR A-type | CR B-type | Absorber | KNI channel |
| MOG1 | $10^3 - 10^2$ | Bottom part 0 – 60 cm | - | Bottom part 0 – 60 cm | - |
| MOG2 | $10^2 - 10^1$ | Part 60 – 120 cm from the bottom | Bottom part 0 – 60 cm | Part 60 – 120 cm from the bottom | Bottom part 0 – 250 cm |
| MOG3 | $10^1 - 10^{-1}$ | CR rest part (360 cm) | CR rest part (420 cm) | ABS rest part (140 cm) | KNI rest part (up to 350 cm) |

CR A-type: from group VI. of controlled rod assemblies – inserted partially in the core



CR B-type: CR from other groups of controlled rod assemblies – occasionally in the core



Absorber



KNI channel




Sampling of activated components in V1 NPP HLW storage – results (2)

Total inventory of CR, ABS and KNI channels placed in V1 NPP HLW storage on due date 1.8.2011:

| Material | Connection rods | | Absorbers | | KNI channels | | Total | |
|--------------|-----------------|-----------|---------------|-----------|---------------|-----------|-----------------|---------------|
| | Activity [Bq] | Mass [kg] | Activity [Bq] | Mass [kg] | Activity [Bq] | Mass [kg] | Activity [Bq] | Mass [kg] |
| MOG1 | 1,07E+15 | 273 | 1,94E+15 | 4 023 | - | - | 3,01E+15 | 4 296 |
| MOG2 | 2,22E+14 | 1 526 | 3,65E+13 | 4 023 | 2,63E+14 | 495 | 5,21E+14 | 6 044 |
| MOG3 | 8,36E+13 | 11 717 | 1,01E+13 | 10 637 | 2,63E+12 | 495 | 9,64E+13 | 22 849 |
| TOTAL | 1,38E+15 | 13 516 | 1,99E+15 | 18 683 | 2,66E+14 | 990 | 3,63E+15 | 33 189 |

RNV valid to date of component unloading from the core and putting to HLW storage



Sampling of reactor and its internals

Subject of sampling:

1. Internals of RPV, Unit 2:

- Protective tube unit
- Core basket
- Reactor cavity

2. Selected shielding assemblies, both units

3. RPV:

- Basic material sampled from outer side in reactor shafts – bottom part, Unit 1, 2
 - Internal cladding of RPV, Unit 2
-
- In total **34 samples taken** – swarf with mass from 0.1 mg to 125 mg
 - Depth of sampling: 2 – 5 mm
 - Remote controlled sampling equipment (the same for HLW storage sampling)
 - Manual drilling with sample capture – only in case of basic RPV material


Sampling of reactor internals, Unit 2



Protective tube unit

Core basket

Reactor cavity



- Container for transport of reactor internals
- Remote controlled sampling carried out on air in refuelling pond above the RPV
- **15 samples taken**
- Dose rate at 50 cm distance:
 - Protective tube unit : 0.44 - 110 mSv/h
 - Core basket: 2400 – 37000 mSv/h
 - Cavity: 0.5 – 4200 mSv/h




Sampling of reactor internals, unit 2– results

Total inventory of reactor internals determined on due date 30.9.2011:


| Component | Parameter | Unit 1 | Unit 2 | Total |
|----------------------|---------------|----------|----------|----------|
| Protection tube unit | Activity [Bq] | 5,69E+14 | 8,37E+14 | 1,41E+15 |
| | Mass [kg] | 27 304 | 27 304 | 54 608 |
| Core basket | Activity [Bq] | 5,84E+16 | 8,59E+16 | 1,44E+17 |
| | Mass [kg] | 22 480 | 22 480 | 44 960 |
| Reactor cavity | Activity [Bq] | 7,41E+15 | 1,09E+16 | 1,83E+16 |
| | Mass [kg] | 61 250 | 61 250 | 122 500 |

RNV Unit 2



Inventory and RNV for Unit 1 recalculated considering different final shutdown

Sampling of shielding assemblies, both units (1)




- **Shielding assemblies** = 36 replaced fuel assemblies in peripheral core position – reduced RA impact on RPV
- **Refuelling machine for transport** of shielding assemblies used
- **Remote controlled sampling** carried out on air in spent fuel storage pool
- Selected 3 assemblies/unit based on their position in the core
- **6 samples taken**

- Dose rate at 50 cm distance: 3.1 – 110 Sv/h

- Confirmed measured dose rates carried in 2008, dose rate at 1cm distance: > 2000 Sv/h

Sampling of shielding assemblies - video




Sampling of shielding assemblies – results


Total inventory of shielding assemblies determined on due date 30.9.2011:

| Component | Parameter | Unit 1 | Unit 2 | Total |
|----------------------|---------------|----------|----------|----------|
| Shielding assemblies | Activity [Bq] | 4,63E+16 | 4,63E+16 | 9,27E+16 |
| | Mass [kg] | 10 800 | 10 800 | 21 600 |


Unit 1



Unit 2



Sampling of RPV – basic material & cladding



Sampling of RPV internal cladding, Unit 2:

- Concrete container inside RPV
- Remote controlled equipment – 7 taken samples
- Dose rate at 50 cm: 1 – 1010 mSv/h

Sampling of RPV basic material, both units:


- Manual drilling - 6 taken samples
- Average dose rate: 100 – 300 μ Sv/h

Sampling of RPV – results


Total inventory of RPV material determined on due date 30.9.2011:

| Component | Parameter | Unit 1 | Unit 2 | Total |
|-----------------------|---------------|----------|----------|----------|
| RPV basic material | Activity [Bq] | 3,36E+14 | 3,97E+14 | 7,33E+14 |
| | Mass [kg] | 247 800 | 247 800 | 495 600 |
| RPV internal cladding | Activity [Bq] | 1,23E+14 | 1,76E+14 | 2,99E+14 |
| | Mass [kg] | 17 300 | 17 300 | 34 600 |

RPV internal cladding, Unit1




RPV basic material, Unit1



Sampling of storage grids in spent fuel cooling pond, Unit 1



- Manual drilling with sample capture on air
- 3 taken samples
- Average dose rate: 350 μ Sv/h
- RNV, Unit 1



Total inventory of storage grids determined on due date 30.9.2011:

| Component | Parameter | Unit 1 | Unit 2 | Total |
|--|---------------|----------|----------|----------|
| Storage grids of spent fuel cooling pond | Activity [Bq] | 4,61E+11 | 7,63E+11 | 1,22E+12 |
| | Mass [kg] | 4 700 | 4 700 | 9 400 |

Radiological Characterization of V1 NPP - Activation

■ Same approach for all activated components:

- Working program
- Work implementation: dose rate measurements, sampling, analyses
- Report - evaluation of working program (including DVD)
- DDB import: **1130** modified or new items

■ Total number of samples: **125**

■ Total inventory: **2,61E+17 Bq**

■ Analyses:

- All samples – gamma-spectrometry
- 13 samples – analysis of hard-to-detect radionuclides:
C-14, Ca-41, Ni-59, Ni-63, Fe-55, Se-79, Sr-90, Mo-93, Zr-93, Nb-94, Tc-99, Pd-107, Sn-126, I-129, Cs-135, Sm-151, Pu-238, Pu-239+240, Am-241, Cm-244 (RA nuclides limited for RAW repository in Mochovce)




Radiological inventory results – activation (1)

Final list of 19 RNV for activation:

- RPV cladding – Unit1, Unit 2
- RPV basic material, water biological shielding - Unit1, Unit 2
- RPV internals - Unit1, Unit 2
- Shielding assemblies - Unit1, Unit 2
- RPV Serpentine - Unit1, Unit 2
- RPV Thermal insulation - Unit1, Unit 2
- Activated standard concrete - Unit1, Unit 2
- Activated baryte concrete - Unit1, Unit 2
- Grids of spent fuel storage pool, stainless steel cladding of reactor shaft - Unit1, Unit 2
- High level waste storage (Mogilnik) – control rods, absorbers, neutron flux measurement channels

Radiological inventory results – activation (2)

Percentage contribution of radionuclides to the NPP V-1 activation:



Other identified activation products:

| Radionuclide | Contribution (%) |
|--------------|------------------|
| Ba-133 | 4,24E-09 |
| Cs-134 | 4,23E-09 |
| Eu-152 | 1,10E-07 |
| Eu-154 | 1,08E-08 |

Thank you for your attention.

Any questions?

