

# Status of the EUROTRANS R&D activities for ADS accelerator development

**Jean-Luc BIARROTTE** – CNRS / IPN Orsay

*On behalf of the EUROTRANS WP1.3 collaboration*

# Accelerator Driven Systems

## 1. Overall purpose


- Reduce the nuclear waste radiotoxicity & volume before underground storage
- 2500 tons of spent fuel are produced every year by the 145 EU reactors

## 2. Available strategy

- Partitioning : chemical separation of Pu, MA & FP
- Transmutation : use of the waste as a fuel in dedicated transmuter systems

## 3. The ADS transmuter system

- A subcritical reactor ( $k < 1$ ), in which the chain reaction is not self-sustained
- An intense spallation source, that provides the “missing” neutrons



# The EUROTRANS programme

- **EUROpean research programme for the TRANsmutation of high level nuclear waste in an Accelerator Driven System**
- EU FP6 programme (2005-2009)
- 31 research agencies & industries, 16 universities
- Expands the EU FP5 project PDS-XADS (2001-2004)
- 5 Domains (DM1=Design, ...)



## Main GOAL of the EUROTRANS programme

- Advanced design of a 50-100 MWth eXperimental facility demonstrating the technical feasibility of Transmutation on an ADS (**XT-ADS, short-term realisation**)
- Generic conceptual design (several 100 MWth) of a European Facility for Industrial Transmutation (**EFIT, long-term realisation**)

# European Transmutation Demonstration


## 1. XT-ADS (ADS prototype)

### Goals:

- **Demonstrate the concept** (coupling between accelerator, spallation target & reactor),
- **Demonstrate the transmutation**
- **Provide an irradiation facility** and an EFIT test bench

### Features:

- 50-100 MWth power
- Keff around 0.95
- 600 MeV, 2.5 mA proton beam (or 350 MeV, 5 mA)
- Conventional MOX fuel
- Lead-Bismuth Eutectic coolant



## 2. EFIT (Industrial Transmuter)

### Goals:

- Maximise the transmutation efficiency
- Easiness of operation and maintenance
- High level of availability for a cost-effective transmutation

### Features:

- Several 100 MWth power
- Keff around 0.97
- 800 MeV, 20 mA proton beam
- Minor Actinide fuel
- Lead coolant (gas as back-up solution)

# Accelerator main specifications

## High-power proton CW beams

Table 1 – XT-ADS and EFIT proton beam general specifications

	XT-ADS	EFIT
Maximum beam intensity	2.5 – 4 mA	20 mA
Proton energy	600 MeV	800 MeV
Beam entry	Vertically from above	
Beam trip number	< 20 per year (exceeding 1 second)	< 3 per year (exceeding 1 second)
Beam stability	Energy: $\pm 1\%$ , Intensity: $\pm 2\%$ , Size: $\pm 10\%$	
Beam footprint on target	Circular $\varnothing$ 5 to 10 cm, "donut-shaped"	An area of up to 100 cm <sup>2</sup> must be "paintable" with any arbitrary selectable intensity profile
Beam time structure	CW, with 200 $\mu$ s zero-current holes every 10 <sup>-3</sup> to 1 Hz, + pulsed mode capability (repetition rate around 50 Hz)	



Extremely high reliability is required !!!

# ADS accelerator reference scheme

## PDS-XADS



**Superconducting linac:** Highly modular and upgradeable (same concept for prototype & industrial scale) ; Excellent potential for reliability ; High efficiency (optimized operation cost)



# Reliability aspects

- **Beam trips longer than 1 sec are forbidden** to avoid thermal stresses & fatigue on the ADS fuel & assembly : less than 5 per 3-month operation cycle (XT-ADS)
  
- **Reliability guidelines have been followed during the ADS accelerator design**
  1. Strong component design & derating
    - All components are derated with respect to technological limitations
    - For every linac main component, a prototype is being designed, built and tested within the EUROTRANS programme
  2. Inclusion of redundancies in critical areas
    - Front-end duplication, Solid-state RF power amplifiers where possible...
  3. Capability of fault-tolerant operation
    - Expected in the highly modular superconducting RF linac (from ~20 MeV)
    - Implies reliable and sophisticated digital RF control systems with preset set points for implementation


# 5 reliability-oriented accelerator tasks



- **Task n°1** : Experimental evaluation of the **proton injector** reliability
- **Task n°2** : Assessment of the reliability performances of the **intermediate-energy** acceleration components
- **Task n°3** : Qualification of the reliability performances of a **high-energy cryomodule** at full power and nominal temperature
- **Task n°4** : Design of a prototypical **RF control system** for fault-tolerant operation of the linear accelerator
- **Task n°5** : Overall coherence of the **accelerator design**, final reliability analysis, cost estimation for XT-ADS & EFIT



# Task 1 - IPHI injector status




- SILHI Source operational (100 mA, 95 kV)
- LEPT tuned
- 3 MeV RFQ section 1 validated
- Fabrication of RFQ sections 2 to 6 on-going
- Installation of RFQ environment in progress
- Installation of diagnostic beam line in progress



# Task 1 - Injector reliability tests

## - Real scale long reliability test run


- Once IPHI fully commissioned (mid 2008), the 3 MeV beam will be continuously operated over a period of **2 months** with beam intensity 20-40mA
- Previous tests on the SILHI source in past years show encouraging results : 162 hours run (30mA, 95keV CW beam) => 1 spark, no beam off, +/-0.2mA stability



80 mA - 85 kV pulsed beam (300µs/200ms)


## - Short beam holes production

- Important issue for ADS technology = time structure with periodic 200µs “beam holes” for on-line sub-criticality measurements
- First successful tests on the SILHI source : Fall/Rise time: 20/30 µs




# Task 2 - Intermediate-energy RF structures

## Intermediate Energy Section (3/5 MeV -> 100 MeV)



### Several candidates to be tested & evaluated

- **Copper DTL IH structures** (front end) : high real estate (Konus BD)
- **Superconducting multi-gap CH structures** (front end) : high real estate + RF efficiency
- **Superconducting spoke cavities** (independently-phased linac) : modularity + RF efficiency
- **Transition energy** to be optimised : 17 MeV ?



Iba



JOHANN WOLFGANG  
UNIVERSITÄT  
FRANKFURT AM MAIN





CNRS

CENTRE NATIONAL  
DE LA RECHERCHE  
SCIENTIFIQUE

## Task 2 - Superconducting spoke cavities

### Test of a fully equipped 350 MHz spoke cavity


- $\beta = 0.15$  spoke cavity prototype **constructed and tested** in vertical cryostat
- installation of the horizontal cryostat CM0 **in progress**
- power coupler **ordered**, tuner **validated**
- 10 kW solid-state RF amplifier **ordered**
- horizontal test in CM0 at high power in **2008**



# Task 2 - Superconducting CH structures

## Test of a 350 MHz superconducting CH structure




- 19-gap prototype **constructed**
- several tests in vertical cryostat **achieved**
- tuner system development **in progress**
- horizontal cryostat adaptation **in progress**



# Task 3 - High-energy cryomodule

## Design, fabrication & test of an elliptical module...


- $\beta = 0.47$  prototype **constructed and tested**
- tuner system fabrication **achieved**
- cryomodule design **in progress**



# Task 3 - High-energy cryomodule

## ... at nominal power

- 150 kW CW RF power coupler **under final design**
- experimental validation of the coupler cooling system (He supercritical)
- 700 MHz RF power source (IOT 80 kW) **ordered**
- cryomodule test at high power in **end 2008 - 2009**




**CNRS**  
CENTRE NATIONAL  
DE LA RECHERCHE  
SCIENTIFIQUE



# Task 4 - RF fault compensation

## Fault-tolerance = ability to loose a RF cavity (or Q-pole) without losing the beam

- Based on the local **compensation method**



- **Demonstrated** on the beam dynamics point of view in the **independently-phased linac**
- Requires up to 30% **margins** on fields and powers
- Need to identify & develop **fast failure recovery scenarios** ( $\ll 1$  sec)
  - Fast fault detection (and beam shut-down)
  - Fast communication between neighbouring LLRF systems
  - Fast update and tracking of the field/phase set-points (preset)
  - Adequate management of the tuner of the failed cavity
  - Beam recovery

**FPGA  
based  
DIGITAL  
SYSTEM**




# Task 4 - Digital LLRF control system

- It of course has also to reduce the effect of all perturbations (frequency fluctuations, beam loading transients...) below around  $\pm 0.5\%$  (fields) and  $\pm 0.5^\circ$  (phase)



- Successful preliminary tests at 350 MHz



Without regulation

With regulation




Figure 2 - Possible generic scheme for the XT-ADS digital RF feedback system.


# Task 5 - Accelerator design

## - GOAL of this task

- Supervise the **overall coherence** of the accelerator design
- Reach an “as much as possible” frozen design with assessed reliability figure and costing in 2009


## - Beam dynamics simulations

- start to end simulations of different options for the intermediate-energy structures
- modeling of beam transients induced by RF faults (implementation in TraceWin)




## - Preliminary costings

- Parametric study to test the energy dependence



# Task 5 - Interface with the reactor

- **Final beam transport line**
  - Connects the linac to the LBE spallation target
  - Guarantees the position of the beam spot and ensures that only particles of nominal energy are delivered (doubly-achromatic line)
  - Guarantees the shape and required distribution at the target (redundant beam scanning)
- **Beam transients effect on fuel claddings and target**
  - Preliminary studies show that beam holes up to 1 sec (from faults or for sub-criticality monitoring) have **negligible effects on core claddings**



# Task 5 - Integrated reliability analysis


- Standard reliability analyses performed on the design
  - **Failure Modes and Effect Analysis (FMEA)** performed on the whole linac to assess critical areas in the design with a bottom-up approach
  - **Reliability Block Diagram (RBD)** analysis to derive reliability estimations of different configurations from top-down, varying in the degree of redundancy and fault-tolerance

A preliminary reliability analysis of the system (PDS-XADS) shows that **the “less than a few beam trips per year”**

**goal is REACHABLE**




Classical linac



System MTBF	31.19 hours
Nb of failures (3 months)	70.23
Steady State Availability	86.6 %


ADS linac, optimized for reliability



System MTBF	757.84 hours
Nb of failures (3 months)	2.89
Steady State Availability	99.5 %

Preliminary reliability estimations by P. Pierini, INFN

# Beyond EUROTRANS...



## ... XT-ADS @ SCK•CEN Mol ?

